COMPLETED EXAMPLE

Baseboard installation estimate

Baseboard replacement in two rooms

BUSINESS
Daniel & Sons

CONTACT DETAILS

CUSTOMER
Sample customer

PROJECT / ADDRESS
Baseboard replacement in two rooms

DOCUMENT REFERENCE
EST-001

DATE / VALID UNTIL

Illustrative USD selling prices. Quantities and rates are examples, not market benchmarks.

Work / material	Qty / unit	Rate	Taxable?	Amount
Protection and old-trim removal Remove old baseboard and protect floors; disposal fee separate.	120 linear ft	$0.75	Yes	$90.00
Baseboard materials Seventeen 8 ft stock lengths give 136 linear ft purchased.	17 lengths	$18.00	Yes	$306.00
Fixings and caulk Fasteners, filler and caulk; no labor.	1 package	$45.00	Yes	$45.00
Cutting and fitting labor Fit 120 linear ft including agreed corner cuts.	120 linear ft	$2.50	Yes	$300.00
Preparation and finishing labor Fill, caulk and paint selected trim; drying is not labor time.	5 hours	$60.00	Yes	$300.00
Paint materials Specified finish and application consumables.	1 package	$55.00	Yes	$55.00
Cleanup and disposal Collect cutoffs and dispose of old trim.	1 job	$65.00	Yes	$65.00

Subtotal	$1,161.00
Tax (0%)	$0.00
Total (USD)	**$1,161.00**

Scope / products / finish

Replace 120 measured linear ft of baseboard in two rooms. Supply selected primed stock, fit to agreed corners, fill and caulk, then apply the specified finish.

Exclusions / allowances

Wall repairs, floor leveling, furniture moving, shoe molding and whole-wall painting excluded. Length schedule excludes door openings.

Schedule / payment / acceptance

Agree the schedule, payment and acceptance arrangements for the actual job.

0% tax is shown for illustration only. Use the applicable tax treatment for your job.

Free template from Construction Job Estimator
constructionjobestimator.com/templates/baseboard-installation-estimate/