COMPLETED EXAMPLE

Bathroom remodel estimate

Bathroom refresh — layout retained

BUSINESS
Daniel & Sons

CONTACT DETAILS

CUSTOMER
Sample customer

PROJECT / ADDRESS
Bathroom refresh — layout retained

DOCUMENT REFERENCE
EST-001

DATE / VALID UNTIL

Illustrative USD selling prices. Quantities and rates are examples, not market benchmarks.

Work / material	Qty / unit	Rate	Taxable?	Amount
Protection and removal Protect access; remove old fixtures and agreed finishes; load waste.	1 job	$1,200.00	Yes	$1,200.00
Fixture fitting package Fit owner-supplied tub, vanity, basin, toilet and taps in existing positions; connections and testing included.	1 package	$1,200.00	Yes	$1,200.00
Electrical work package Qualified trade replaces owner-supplied fan and light using assessed existing connections and duct route.	1 package	$650.00	Yes	$650.00
Backing and waterproofing Specified substrate and waterproofing system; materials and installation included.	1 package	$1,200.00	Yes	$1,200.00
Tile supply 10 sq ft per box: 180 sq ft purchased for 160 sq ft installed.	18 boxes	$40.00	Yes	$720.00
Tile installation Labor, adhesive, grout and edge trims included; excludes tile and backing/waterproofing above.	160 sq ft	$12.00	Yes	$1,920.00
Painting and finish details Paint ceiling and untiled walls; refit retained accessories; labor and consumables included.	1 package	$700.00	Yes	$700.00
Disposal and final clean Waste haul and disposal fees, final cleaning and handover; removal labor is above.	1 job	$350.00	Yes	$350.00

Subtotal	$7,940.00
Tax (0%)	$0.00
Total (USD)	**$7,940.00**

Scope / products / finish

Replace finishes and owner-supplied fixtures in existing positions. Include 40 sq ft floor tile and 120 sq ft wall tile, specified backing and waterproofing, fixture fitting, limited electrical work, painting and cleanup.

Exclusions / allowances

Owner supplies the bathtub, vanity, basin, toilet, taps, fan and light. Structural work, concealed damage, service relocation, new circuits or duct routes, shower glazing and permit fees are excluded. Confirm approval responsibilities before acceptance.

Schedule / payment / acceptance

Agree the schedule, payment and acceptance arrangements for the actual job.

0% tax is shown for illustration only. Use the applicable tax treatment for your job.

Free template from Construction Job Estimator
constructionjobestimator.com/templates/bathroom-remodel-estimate/