COMPLETED EXAMPLE

Cabinet painting estimate

Existing kitchen cabinets repainted

BUSINESS
Daniel & Sons

CONTACT DETAILS

CUSTOMER
Sample customer

PROJECT / ADDRESS
Existing kitchen cabinets repainted

DOCUMENT REFERENCE
EST-001

DATE / VALID UNTIL

Illustrative USD selling prices. Quantities and rates are examples, not market benchmarks.

Work / material	Qty / unit	Rate	Taxable?	Amount
Protection and labeling Mask the work area and label doors, fronts and hardware.	4 hours	$60.00	Yes	$240.00
Cleaning and preparation Degrease and prepare the 24 removable pieces and frames.	12 hours	$60.00	Yes	$720.00
Primer and coating materials Selected cabinet primer, finish and preparation consumables.	1 package	$360.00	Yes	$360.00
Door and drawer coating labor 18 doors plus 6 fronts; both faces and edges included.	24 pieces	$45.00	Yes	$1,080.00
Frame coating labor Exposed frames and agreed end panels; interiors excluded.	24 linear ft	$15.00	Yes	$360.00
Equipment hire Coating equipment hire; labor is priced separately.	1 job	$140.00	Yes	$140.00
Refitting and final check Refit retained hardware, align doors and inspect finish.	5 hours	$60.00	Yes	$300.00

Subtotal	$3,200.00
Tax (0%)	$0.00
Total (USD)	**$3,200.00**

Scope / products / finish

Label and remove 18 doors and 6 drawer fronts. Clean, prepare, prime and apply two finish coats to both faces and edges, plus exposed frames and end panels. Refit existing hardware.

Exclusions / allowances

Cabinet interiors, new cabinets, new hardware, damaged veneer repairs, countertops and wall painting excluded. Confirm finish compatibility and curing requirements.

Schedule / payment / acceptance

Agree the schedule, payment and acceptance arrangements for the actual job.

0% tax is shown for illustration only. Use the applicable tax treatment for your job.

Free template from Construction Job Estimator
constructionjobestimator.com/templates/cabinet-painting-estimate/