COMPLETED EXAMPLE

Chain-link fence installation estimate

Straight chain-link fence with one gate

BUSINESS
Daniel & Sons

CONTACT DETAILS

CUSTOMER
Sample customer

PROJECT / ADDRESS
Straight chain-link fence with one gate

DOCUMENT REFERENCE
EST-001

DATE / VALID UNTIL

Illustrative USD selling prices. Quantities and rates are examples, not market benchmarks.

Work / material	Qty / unit	Rate	Taxable?	Amount
Chain-link fabric Two 50 ft rolls purchased; 96 ft installed at specified height and mesh.	2 rolls	$150.00	Yes	$300.00
Posts and caps Approved schedule: four terminal posts and eight line posts with caps.	1 package	$420.00	Yes	$420.00
Rails and fittings Specified rail lengths, ties, tension components and connectors.	1 package	$310.00	Yes	$310.00
Concrete and footing materials Materials allowance for approved footing schedule; no universal footing size.	1 package	$160.00	Yes	$160.00
Gate and hardware Selected 4 ft gate assembly and hardware.	1 set	$220.00	Yes	$220.00
Layout and post installation Person-hours for agreed layout, excavation and post work.	16 hours	$65.00	Yes	$1,040.00
Fabric and gate installation Fit fabric, rails, fittings and gate to selected system.	10 hours	$65.00	Yes	$650.00
Cleanup and disposal Ordinary spoil handling and final cleanup.	1 job	$100.00	Yes	$100.00

Subtotal	$3,200.00
Tax (0%)	$0.00
Total (USD)	**$3,200.00**

Scope / products / finish

Install an assessed straight 100 ft boundary comprising 96 ft of chain-link fence and one 4 ft gate opening. Use the approved post and footing schedule, specified fabric, rails and fittings. No existing fence removal.

Exclusions / allowances

Surveying, permits, utility relocation, rock excavation, retaining work and unusual access excluded. Confirm boundary, underground services and system-specific layout before work.

Schedule / payment / acceptance

Agree the schedule, payment and acceptance arrangements for the actual job.

0% tax is shown for illustration only. Use the applicable tax treatment for your job.

Free template from Construction Job Estimator
constructionjobestimator.com/templates/chain-link-fence-installation-estimate/