COMPLETED EXAMPLE

Commercial office painting estimate

Phased office wall repaint

BUSINESS
Daniel & Sons

CONTACT DETAILS

CUSTOMER
Sample customer

PROJECT / ADDRESS
Phased office wall repaint

DOCUMENT REFERENCE
EST-001

DATE / VALID UNTIL

Illustrative USD selling prices. Quantities and rates are examples, not market benchmarks.

Work / material	Qty / unit	Rate	Taxable?	Amount
Protection and phase setup Protect work zones and set up both agreed phases.	8 hours	$65.00	Yes	$520.00
Localized wall repairs Repair the scheduled minor defects; no full skim.	6 hours	$65.00	Yes	$390.00
Primer and repair materials Selected spot primer, filler and preparation supplies.	1 package	$160.00	Yes	$160.00
Wall finish paint Sample purchase for the specified two-coat wall finish.	12 US gal	$48.00	Yes	$576.00
Paint application Person-hours for the measured walls, including cutting in and both coats.	32 hours	$65.00	Yes	$2,080.00
Return setup and coordination Agreed additional handling between phases; not application time.	4 hours	$65.00	Yes	$260.00
Consumables Tape, sheeting and application consumables.	1 package	$110.00	Yes	$110.00
Final check and cleanup Agreed touchups, protection removal and final handover.	4 hours	$65.00	Yes	$260.00

Subtotal	$4,356.00
Tax (0%)	$0.00
Total (USD)	**$4,356.00**

Scope / products / finish

Repaint 2,000 measured sq ft of office walls in two agreed evening access phases. Include protection, localized repairs, spot primer and two specified finish coats. Client clears furniture from work zones.

Exclusions / allowances

Ceilings, doors, trim, full skim coating, furniture moving and hazardous coatings excluded. Extra access phases or client delays require an agreed change.

Schedule / payment / acceptance

Agree the schedule, payment and acceptance arrangements for the actual job.

0% tax is shown for illustration only. Use the applicable tax treatment for your job.

Free template from Construction Job Estimator
constructionjobestimator.com/templates/commercial-office-painting-estimate/