COMPLETED EXAMPLE

Composite deck installation estimate

Composite decking on an assessed existing frame

BUSINESS
Daniel & Sons

CONTACT DETAILS

CUSTOMER
Sample customer

PROJECT / ADDRESS
Composite decking on an assessed existing frame

DOCUMENT REFERENCE
EST-001

DATE / VALID UNTIL

Illustrative USD selling prices. Quantities and rates are examples, not market benchmarks.

Work / material	Qty / unit	Rate	Taxable?	Amount
Old deck surface removal Remove existing surface boards; frame retained.	192 sq ft	$1.50	Yes	$288.00
Composite deck boards Approved cut schedule: 26 installed 16 ft boards plus one spare.	27 boards	$65.00	Yes	$1,755.00
Fascia boards Four 12 ft stock boards for 40 ft exposed perimeter.	4 boards	$85.00	Yes	$340.00
Fasteners and edge details Selected system's specified clips, screws and edge accessories.	1 package	$240.00	Yes	$240.00
Decking installation labor Fit the approved board schedule to assessed frame.	24 hours	$65.00	Yes	$1,560.00
Fascia and detail labor Fit agreed perimeter fascia and finish details.	6 hours	$65.00	Yes	$390.00
Cleanup and disposal Ordinary old-board disposal and final cleanup.	1 job	$180.00	Yes	$180.00

Subtotal	$4,753.00
Tax (0%)	$0.00
Total (USD)	**$4,753.00**

Scope / products / finish

Install selected composite deck boards and fascia on an existing frame assessed as suitable for the chosen system. Include agreed removal of old surface boards, the approved board/fastener schedule and finish details. No new structural frame.

Exclusions / allowances

Footings, framing replacement, structural design, stairs, guardrails and concealed frame repairs excluded. Reprice if inspection or removal reveals unsuitable framing. This is a surface replacement estimate, not a full new-deck price.

Schedule / payment / acceptance

Agree the schedule, payment and acceptance arrangements for the actual job.

0% tax is shown for illustration only. Use the applicable tax treatment for your job.

Free template from Construction Job Estimator
constructionjobestimator.com/templates/composite-deck-installation-estimate/