COMPLETED EXAMPLE

Deck repair estimate

Localized timber deck-board replacement

BUSINESS
Daniel & Sons

CONTACT DETAILS

CUSTOMER
Sample customer

PROJECT / ADDRESS
Localized timber deck-board replacement

DOCUMENT REFERENCE
EST-001

DATE / VALID UNTIL

Illustrative USD selling prices. Quantities and rates are examples, not market benchmarks.

Work / material	Qty / unit	Rate	Taxable?	Amount
Setup and protection Protect access and mark the eight boards agreed for replacement.	2 hours	$65.00	Yes	$130.00
Board removal Remove specified boards without treating retained framing as confirmed sound.	3 hours	$65.00	Yes	$195.00
Replacement board materials Eight selected 12 ft boards; 96 linear ft purchased.	8 boards	$28.00	Yes	$224.00
Fasteners and consumables Compatible fixings and required cut-end treatment.	1 package	$75.00	Yes	$75.00
Board fitting labor Cut and fit replacement boards to the verified support arrangement.	6 hours	$65.00	Yes	$390.00
Delivery and disposal fees Delivery and waste charges; removal labor priced above.	1 job	$95.00	Yes	$95.00
Cleanup and handover Tidy and document completed board repairs.	1 hour	$65.00	Yes	$65.00

Subtotal	$1,174.00
Tax (0%)	$0.00
Total (USD)	**$1,174.00**

Scope / products / finish

Replace eight identified deck boards with eight selected 12 ft boards. Include careful removal, compatible fasteners, fitting and disposal. Retain the existing framing subject to inspection.

Exclusions / allowances

Joists, beams, posts, footings, ledger, stairs, guardrails and whole-deck finishing excluded. Hidden framing defects require reassessment; this estimate is not a structural certification.

Schedule / payment / acceptance

Agree the schedule, payment and acceptance arrangements for the actual job.

0% tax is shown for illustration only. Use the applicable tax treatment for your job.

Free template from Construction Job Estimator
constructionjobestimator.com/templates/deck-repair-estimate/