Kitchen backsplash installation estimate

COMPLETED EXAMPLE

Straight-layout kitchen backsplash

BUSINESS
Daniel & Sons

CONTACT DETAILS

CUSTOMER
Sample customer

PROJECT / ADDRESS
Straight-layout kitchen backsplash

DOCUMENT REFERENCE
EST-001

DATE / VALID UNTIL

Illustrative USD selling prices. Quantities and rates are examples, not market benchmarks.

Work / material	Qty / unit	Rate	Taxable?	Amount
Protection and layout Protect counters and confirm straight tile layout and cutout positions.	3 hours	$65.00	Yes	$195.00
Local substrate preparation Agreed localized preparation labor and materials; not full wall replacement.	1 package	$180.00	Yes	$180.00
Tile materials 8 sq ft per box:48 sq ft bought for 40 sq ft installed.	6 boxes	$48.00	Yes	$288.00
Setting and grout materials Selected compatible adhesive, grout and sealant; no labor included.	1 package	$110.00	Yes	$110.00
Edge trim materials Selected exposed-edge trim; fitting included in setting labor.	12 linear ft	$5.00	Yes	$60.00
Tile setting labor Straight layout, four outlet cutouts and edge fitting included.	40 sq ft	$18.00	Yes	$720.00
Grouting and cleanup Grout, finish agreed junctions and clean; drying is not hands-on labor.	4 hours	$65.00	Yes	$260.00

Subtotal	$1,813.00
Tax (0%)	$0.00
Total (USD)	**$1,813.00**

Scope / products / finish

Install 40 sq ft of selected backsplash tile on assessed walls, including four outlet cutouts and 12 linear ft of exposed edges. Include local substrate preparation, setting materials, grouting and cleanup.

Exclusions / allowances

Old tile removal, full wall replacement, electrical device alterations, countertop work, patterned layouts and concealed damage excluded. Electrical work is arranged separately where required.

Schedule / payment / acceptance

Agree the schedule, payment and acceptance arrangements for the actual job.

0% tax is shown for illustration only. Use the applicable tax treatment for your job.

Free template from Construction Job Estimator
constructionjobestimator.com/templates/kitchen-backsplash-installation-estimate/