COMPLETED EXAMPLE

Vinyl plank flooring installation estimate

Living room and hallway vinyl plank

BUSINESS
Daniel & Sons

CONTACT DETAILS

CUSTOMER
Sample customer

PROJECT / ADDRESS
Living room and hallway vinyl plank

DOCUMENT REFERENCE
EST-001

DATE / VALID UNTIL

Illustrative USD selling prices. Quantities and rates are examples, not market benchmarks.

Work / material	Qty / unit	Rate	Taxable?	Amount
Carpet removal and handling Remove carpet and load waste; disposal fee is separate.	300 sq ft	$0.65	Yes	$195.00
Limited subfloor preparation Agreed localized patching labor and materials; not full leveling.	1 package	$180.00	Yes	$180.00
Vinyl plank materials 24 sq ft per box: 336 sq ft purchased for 300 sq ft installed.	14 boxes	$66.00	Yes	$924.00
Flooring installation labor Install selected planks; materials and trim fitting are separate.	300 sq ft	$2.50	Yes	$750.00
Trim supply and fitting Selected shoe molding with fitting and fixings included.	80 linear ft	$3.50	Yes	$280.00
Transition supply and fitting Three agreed doorway transitions; labor included.	3 pieces	$55.00	Yes	$165.00
Delivery and disposal fees Supplier delivery and waste charges; removal handling above.	1 job	$110.00	Yes	$110.00
Cleanup and handover Final cleanup and product care information.	1 job	$70.00	Yes	$70.00

Subtotal	$2,674.00
Tax (0%)	$0.00
Total (USD)	**$2,674.00**

Scope / products / finish

Remove existing carpet from 300 sq ft and install selected click-lock vinyl plank in the living room and hall. Include an inspected limited patching allowance, 80 linear ft trim and three transitions.

Exclusions / allowances

Furniture moving, stair work, structural subfloor repairs, moisture remediation and door trimming excluded. Product has attached pad; any additional layer must be permitted by its installation instructions.

Schedule / payment / acceptance

Agree the schedule, payment and acceptance arrangements for the actual job.

0% tax is shown for illustration only. Use the applicable tax treatment for your job.

Free template from Construction Job Estimator
constructionjobestimator.com/templates/vinyl-plank-flooring-installation-estimate/