COMPLETED EXAMPLE

Wallpaper removal and painting estimate

Wallpaper removal and room repaint

BUSINESS
Daniel & Sons

CONTACT DETAILS

CUSTOMER
Sample customer

PROJECT / ADDRESS
Wallpaper removal and room repaint

DOCUMENT REFERENCE
EST-001

DATE / VALID UNTIL

Illustrative USD selling prices. Quantities and rates are examples, not market benchmarks.

Work / material	Qty / unit	Rate	Taxable?	Amount
Protection and setup Protect floor and retained surfaces.	3 hours	$60.00	Yes	$180.00
Wallpaper removal labor Remove the assessed single layer from agreed walls.	12 hours	$60.00	Yes	$720.00
Adhesive cleaning and local repairs Clean adhesive and make scheduled minor repairs.	6 hours	$60.00	Yes	$360.00
Removal and repair supplies Agreed removal supplies, filler and abrasives.	1 package	$95.00	Yes	$95.00
Primer and finish paint Selected primer and finish paint for specified wall system.	1 package	$215.00	Yes	$215.00
Priming and painting labor Apply agreed primer and two finish coats.	10 hours	$60.00	Yes	$600.00
Cleanup and disposal Protection removal, final cleanup and ordinary waste fees.	1 job	$100.00	Yes	$100.00

Subtotal	$2,270.00
Tax (0%)	$0.00
Total (USD)	**$2,270.00**

Scope / products / finish

Remove one assessed wallpaper layer from 360 sq ft of walls, clean adhesive, complete scheduled localized repairs, prime and apply two specified finish coats. Test-area findings inform the agreed scope.

Exclusions / allowances

Extra paper layers, full skim coating, board replacement, hidden damp, ceilings, trim and hazardous-material work excluded. Reprice unexpected substrate damage before proceeding.

Schedule / payment / acceptance

Agree the schedule, payment and acceptance arrangements for the actual job.

0% tax is shown for illustration only. Use the applicable tax treatment for your job.

Free template from Construction Job Estimator
constructionjobestimator.com/templates/wallpaper-removal-painting-estimate/